

NOTES:

- (A) CONTRACTOR MAY USE CONTINUOUS BAR AND OMIT SPLICES(WHERE POSSIBLE)
 AS LONG AS THE SUBSEQUENT SECHEDULED SPLIC LOCATION REMAINS UNCHANGED.
- (B) REFER TO TYPICAL BEAM ELEVATION DETAIL FOR BEAM STIRRUPS SIZE AND SPACING REQUIREMENT, UNLESS NOTED OTHERWISE ON BEAM SCHEDULE.

